

BEST MANAGEMENT
PRACTICES FOR
URBAN STORMWATER
RUNOFF

*New Hampshire Department of Environmental Services
Water Supply and Pollution Control Division*

January 1996



BEST MANAGEMENT PRACTICES
FOR
URBAN STORMWATER RUNOFF

JANUARY 1996

STATE OF NEW HAMPSHIRE
DEPARTMENT OF ENVIRONMENTAL SERVICES
6 HAZEN DRIVE, P. O. BOX 95
CONCORD, NH 03302-0095

ROBERT W. VARNEY, COMMISSIONER
DANA BISBEE, ASSISTANT COMMISSIONER

NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES
WATER SUPPLY AND POLLUTION CONTROL DIVISION
EDWARD J. SCHMIDT, P.E., Ph.D., DIRECTOR

PREPARED BY:
JAMES T. SPAULDING, P.E.
WASTEWATER ENGINEERING BUREAU

PRINTED ON RECYCLED PAPER

TABLE OF CONTENTS

<u>CHAPTER</u>	<u>PAGE</u>
LIST OF FIGURES	ii
LIST OF TABLES	iii
ACKNOWLEDGMENTS	iv
INTRODUCTION	v
CHAPTER 1: THE IMPACTS OF URBAN RUNOFF	I-1
CHAPTER 2: STORMWATER QUANTITY	II - 1
CHAPTER 3: VEGETATED FILTER STRIPS	III - 1
CHAPTER 4: GRASSED SWALES	IV - 1
CHAPTER 5: EXTENDED DETENTION PONDS	V - 1
CHAPTER 6: WET PONDS	VI - 1
CHAPTER 7: CONSTRUCTED WETLANDS	VII-1
CHAPTER 8: INFILTRATION PRACTICES	VIII - 1
CHAPTER 9: WATER QUALITY INLETS	IX-1
SITE SPECIFIC PROGRAM FACT SHEETS	APPENDIX A

LIST OF FIGURES

<u>FIGURE</u>	<u>PAGE</u>
2.1: Changes in Watershed Hydrology as a Result of Urbanization	II-5
3.1: Schematic of a vegetated Filter Strip	III-4
4.1: Schematic of a Grassed Treatment Swale	IV-3
5.1: Schematic of an Extended Detention Basin with Marsh	V-4
6.1: Schematic of a Wet Pond	VI-5
7.1: Schematic of a Constructed Wetland	VII-5
8.1: Schematic of an Infiltration Trench	VIII-6
8.2: Schematic of an Infiltration Basin	VIII-6
9.1: Schematic of a Water Quality Inlet	IX-3

LIST OF TABLES

<u>TABLE</u>	<u>PAGE</u>
RI Dept. of Environmental Management List of Pollutant Concentrations in Urban Runoff . . .	I-2
Annual Storm Pollutant Export, Simple Method	I-3
USEPA Sources of Urban Pollutants	I-5
Percent Removals for Vegetated Filter Strips	III-1
Percent Removals for Grassed Swales	IV-1
Percent Removals for Extended Detention Ponds	V-1
Percent Removals for Wet Ponds	VI-1
Percent Removals for Constructed Wetlands	VII-1
Percent Removals for Infiltration Trenches	VIII-1
Percent Removals for Infiltration Basins	VIII-2
Percent Removals for Water Quality Inlets	IX-1